



राष्ट्रीय प्रौद्योगिकी संस्थान - आंध्रप्रदेश
NATIONAL INSTITUTE OF TECHNOLOGY ANDHRA PRADESH
Near National Highway No. 16, Kadakatla, Tadepalligudem – 534101
West Godavari District, Andhra Pradesh

Ref. No.: NITANP/SMMD/TENDER/2025-26/ 29

Date: 28.07.2025

TENDER ENQUIRY

Sub: Providing and fixing the false ceiling for library & PMMM , Laying of tiles in Vamsadhara (BH) and miscellaneous glass work in various departments at NIT Andhra Pradesh- Quotation invited –Regd.

Please send your lowest quotation for the above work as per the details attached in **Annexure-1**. The quotation is to be sent in a sealed envelope to the following address:

**C/o Tender Box
Material Management & Disposal Section,
Sardar Vallabhbhai Patel Administrative Building
NATIONAL INSTITUTE OF TECHNOLOGY, ANDHRA PRADESH,
Near National Highway No. 16, Kadakatla,
TADEPALLIGUDEM – 534101
West Godavari District, Andhra Pradesh.**

The quotation has to be sent by Post (Ordinary / Register / Speed Post) or drop in Tender Box physically. (Any other mode will not be accepted)

The envelope must be superscribed as “**QUOTATION**” at the center of the envelope and the above **reference number at left top** along with the name of the tender on the envelope. Quotations without the above superscription **will not be accepted**.

The last date to receive the sealed quotation is 18.08.2025

Annexure-1

Work No:01

Name of the Work: Miscellaneous Glass work in civil workshop & PMMM Complex, New boys Hostel at NIT, Andhra Pradesh					
S No	Description Of Items	Units	Qty	Rate (Rs.)	Amount (Rs.)
1	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item):				
	With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm)				
	For PMMM Room No:218 & 210 (C)-(Window)	sqm	2.20		
	For Civil work shop-(Window)	sqm	1.97		
	For Nagavalli block Third floor-(Window)	sqm	1.68		
			5.85		
2	Providing and fixing factory made uPVC door frame made of UPVC extruded sections having an overall dimension as below (tolerance ± 1 mm), with wall thickness 2.0 mm (± 0.2 mm), corners of the door frame to be Jointed with galvanized brackets and stainless steel screws, joints mitred and Plastic welded. The hinge side vertical of the framesreinforced by galvanized M.S. tube of size 19 X 19 mm and 1mm (± 0.1 mm) wall thickness and 3 nos. stainless steel hinges fixed to the framecomplete as per manufacturer's specification and direction of Engineerin-charge Extruded section profile size 42x50 mm	Mtrs	10.05		
3	Masquto mess	sqm	0.63		
	Aluminium plastic knobs for exhaust windows	No's	40.00		
GST @ 18%					
Grand Total					

Work No:02

Name of the Work: False ceiling for Library & PMMM at NIT Andhra Pradesh					
S NO	Description of Items	Units	Quantity	Unit Rate (Rs.)	Amount (Rs.)
1	Providing and fixing mineral fibre false ceiling tiles at all heights of size595X595mm of approved texture, design and pattern. The tiles should have Humidity Resistance (RH) of 99%, Light Reflectance ? 85%, Thermal Conductivity k = 0.052 - 0.057 w/m K, Fire Performance as per (BS 476 pt - 6 &7)in true horizontal level suspended on interlockingT-Grid of hot dipped all round galvanized iron section of 0.33 mm thick (galvanized @120 gsm) comprising of main T runners of 15x32 mm of length 3000 mm, cross T of size 15x32mm of length 1200 mm and secondary intermediate cross T of size 15x32 mm of length 600 mm to				

form grid module of size 600x600 mm suspended from ceiling using galvanized mild steel item (galvanised@80gsm) 50 mm long 8mm outer diameter M-6 dash fasteners, 6 mm diameter fully threaded hanger rod up to 1000 mm length and L-shape level adjuster of size 85x25x2 mm, spaced at 1200 mm centre to centre along main 'T'. The system should rest on periphery walls /partitions with the help of GI perimeter wall angle of size 24x24X3000 mm made of 0.40 mm thick sheet, to be fixed to the wall with help of plastic rawl plug at 450 mm centre to centre & 40 mm long dry wall S.S. screws. The exposed bottom portion of all T-sections used in false ceiling support system shall be pre-painted with polyester baked paint, for all heights. The work shall be carried out as per specifications, drawings and as per directions of the engineer-in-charge.

With 16 mm thick beveled tegular mineral fibre false ceiling tile (NRC 0.55 to 0.6)

	Details of calculation				
	Total Area	sqm			
	False ceiling for library	sqm	38.88		
	False ceiling for Pmmm room no:229-A	sqm	9.0		
	Total Quantity		47.88		
GST @ 18%					
Grand Total					

Work No:03

Name of The Work: Laying of tiles in Vamsadhara (BH) , room no. 111 at NIT Andhra Pradesh					
S NO	Description of Items	Units	Qty	Unit Rate (Rs.)	Amount (Rs.)
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.				
	For thickness of tiles above 25 mm and up to 40 mm	sqm	9.30		
2	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete.				
	Size of Tile 600x600 mm	sqm	9.30		
GST @ 18%					
Grand Total					

Note: Bidder must have any one of the below registration certificates

- CPWD class V civil or above
- Any state government PWD class V civil or above

While sending your lowest quotation – please specify the following:

- Sales Tax : Inclusive
GST : Indicate prevailing tax on percentage basis.
- Excise Duty :
- Rates
a) F.O.R. Destination/

- b) Estimated Packing, Forwarding and Freight Charges in case of Ex-works only, may be mentioned on percentage basis.
4. Insurance : Inclusive/ indicate on percentage basis, in case payable by the Institute.
 5. Preferred terms of payment (institute rules permit to pay on Receipt of materials in good condition/completion of the work):
 6. Recommended mode of transport :
 7. Discount offered, if any :
 8. Validity of the offer :
 9. Firm schedule of completion of work :
 10. Detailed drawings / catalogues / Leaflets / literature / samples may be furnished wherever feasible / required.
 11. Please indicate clearly whether the rates quoted herein are the same as applicable to DGS & D / Government Department / Other Public Sector Undertakings.
 12. The supplier shall invariably furnish the **Certificate of Clearance of GST Registration number along with the quotations.**
 13. The quotation should not contain any handwritten text except the Price quoted.
 14. **Rates should be clearly quoted against each Work No under the respective item.**
 15. All the Submitted documents must be duly signed by the bidder along with the firm's seal.
 16. Please mention the Quotation number and name of the item/s (in brief) on your envelope when submitting your quotation to the Institute
 17. Please note that the Director reserves the right to modify or alter the specifications and also to reject any or all the Quotations without assigning any reasons thereto.
 18. The suppliers / firms are informed not to call on us without prior appointment.
 19. The Institute is not responsible for delays / loss in postal transit or due to any other reasons.
 20. Any Violation in the terms and conditions, the bidder will be made ineligible for the contract.



Yours faithfully,

Head of the Department
 सह अधिष्ठाता / Associate Dean
CENTRAL STORES & PURCHASE SECTION
NIT Andhra Pradesh