



राष्ट्रीय प्रौद्योगिकी संस्थान आंध्रप्रदेश
NATIONAL INSTITUTE OF TECHNOLOGY ANDHRA PRADESH
 Near National Highway No. 16, Kadakatla, Tadepalligudem – 534101
 West Godavari District, Andhra Pradesh, India



Ref. No.: NITANP/SMMD/TENDER/2026-27/20

Date: 30.07.2026

TENDER ENQUIRY

Sub: Work for Construction of the Concrete Platform & Extension of Platform for Bio-Technology Department in C.V Raman Building at NIT Andhra Pradesh - Quotation invited –Reg.

Please send your lowest quotation for the above work/supply as per the specifications/requirements mentioned in **Annexure-1**. The lowest quotation must be submitted **ON FIRM LETTER HEAD** in the given format (**Annexure-1 along with necessary documents as specified and duly abiding to the important instructions**), failing which bid shall be treated as Unresponsive. The quotation is to be sent in a sealed envelope to the following address:

**C/o Tender Box
 Material Management & Disposal Section (006, Ground Floor)
 Sardar Vallabhbhai Patel Administrative Building
 National Institute of Technology Andhra Pradesh,
 Near National Highway No. 216A, Kadakatla,
 Tadepalligudem – 534101
 West Godavari District, Andhra Pradesh.**

The quotation has to be sent by Post (Ordinary / Register / Speed Post) or drop in Tender Box physically. (Any other mode will not be accepted)

The envelope must be superscribed as “**QUOTATION**” at the center of the envelope and the above **reference number at left top** along with the **Subject of the tender** on the envelope.

Please note that, the bid envelope received without the above-mentioned superscription **shall be treated as UNRESPONSIVE**.

The last date to receive the sealed envelope with quotation is **20.08.2026**

Annexure-A

Name of the Item/Work: Work for Construction of the Concrete Platform for Bio-Technology Department in C.V Raman Building at NIT Andhra Pradesh.

S. No	Description of Work	Units	Qty	Unit Price (In Rs)	Amount (In Rs)
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 meters lead as per direction of Engineer - in- charge	Cum	0.036		
2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in: Cement mortar 1:4 (1 cement: 4 coarse sand)	Cum	0.684		
3	15 mm cement plaster on the rough side of single or half brick wall of mix:1:4 (1 cement: 4 fine sand)	Sqm	9.18		
4	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/liter and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm.	Sqm	14.7		
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	56.304		
6	Centering and shuttering including strutting, propping etc. and removal of form for Suspended floors, roofs, landings, balconies and access platform	Sqm	5.52		
7	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size de rived from natural sources)	Cum	0.552		
Sub Total (A)					

Annexure-B

Name of the Item/Work: Work for Extension of Platform for Bio-Technology Department in C.V Raman Building at NIT Andhra Pradesh.

S. No	Description of Work	Units	Qty	Unit Price (In Rs)	Amount (In Rs)
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 meters lead as per direction of Engineer - in- charge	Cum	0.072		
2	Brick work with common burnt clay F.P.S. (non-modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum	0.684		
3	15 mm cement plaster on the rough side of single or half brick wall of mix :1:4 (1 cement: 4 fine sand)	Sqm	19.44		
4	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm.	Sqm	25.2		
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	47.23		
6	Centering and shuttering including strutting, propping etc. and removal of form for Suspended floors, roofs, landings, balconies and access platform	Sqm	2.88		
7	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size de rived from natural sources)	Cum	0.288		
8	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with	Sqm	4.86		

	matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish etc. complete at all levels Granite stone slab of colour black, Cherry/Ruby red				
Sub Total (B)					
GST__%					
Grand Total					

The Firm/Bidder must submit following documents along with Quotation failing which bid shall be treated as UNRESPONSIVE:

1. Certificate of GST Registration.
2. Copy of the tender document and enclosures with Bidder's signature and seal.
3. The Bidder must have a Valid Civil Class-V Registration Certificate issued by a state or Central Government like CPWE/PWD.

Important Instructions:

1. L1 will be identified based on the consolidated quoted price if otherwise not specified in the bid document.
2. The quotation should not contain any handwritten text except the Price quoted.
3. Rates should be clearly quoted against each item.
4. The quotation shall be valid for a minimum period of 90 Days from the closing date of the Bid.
5. The price quoted should be F.O.R. Destination (including Freight, insurance, loading, and unloading at specific location in the premises of NIT Andhra Pradesh).
6. The Bidder shall inscribe the Tender reference number and Tender Subject on the bid envelope submitted to the Institute.
7. Please note that the Director reserves the right to modify or alter the specifications and also to reject any or all the Quotations without assigning any reasons thereto.
8. The Institute is not responsible for delays / loss in postal transit or due to any other reasons in regard to timely receipt of the bid.

Sd/-
Associate Dean, P&D (SMMD)